




राजस्थान केन्द्रीय विश्वविद्यालय
Central University of Rajasthan
NH-8, Bandarsindri, Kishangarh-305817, Ajmer(Raj.)



NIT No. CURAJ/R/F.161/2024/2002

Date: 19.09.2024

Financial Bid

Name of Work: Preparation of Ground for the installation of turf on badminton court at Hostel B-5, B-6 & B-7 at Central University of Rajasthan.

S. N	Description	Qty	Unit	Rate	Amount
1	Taking out existing CC interlocking paver blocks from footpath/ central verge, court yard including removal of rubbish etc., disposal of unserviceable material to the dumping ground, and stacking of serviceable material within 200 metre lead as per direction of Engineer-in-Charge.	337.50	Sqm		
2	Preparation and consolidation of sub grade with plate vibrator after excavating earth to an average of 30 cm depth if any required, dressing of area of even surface and consolidating with plate vibrator including making good the undulations etc. and leveling the sub grade and disposal of surplus earth with lead upto 200 metres.	337.50	Sqm		
3	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.				
3.1	All kinds of soil	3.38	Cum		
4.0	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level				
4.1	1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	34.26	Cum		
5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering, finishing, glass strips/marble strip for expansion joint, concrete should be placed in panels by providing expansion joint of size 12mm wide and 40mm deep - All work up to plinth level :				
5.1	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources).	50.63	Cum		
Total Rs. (in Figures): Total Rupees(in words):					

Note:

1. The Goods and Service Tax, Turnover Tax, Excise Duty, Work Contract Tax, Or any other Tax as applicable shall be paid by the contractor himself. **The bidder shall quote his rates considering all such Taxes.**

Seal & Signature of Bidder

Date: